

1 070514

2-22-88

142 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,177-0000

C SE SE, SEC. 32, T 31 S, R 11 W/E
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020

Lease Name Cooper Well # 1-32

Operator: Rine Exploration Company
Name & Address 300 West Douglas, Suite 645
Wichita, KS 67202

County Barber 14463
Well Total Depth 4450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929

Address 205 East Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 9:10 p.m. Day: 22 Month: 2 Year: 19 88

Plugging proposal received from John Armbruster

(company name) Duke Drilling Company (phone) 316-267-1331
Elevation 1569'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 820-40'

1st plug at 840' with 50 sx cement,

2nd plug at 280' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:30 p.m. Day: 22 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 840' with 50 sx cement,

2nd plug at 280' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

2-24-88

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED
Should be observed this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE 2-29-88

INV. NO. 19943

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

Expected Spud Date. 02 13 88
month day year

(see rules on reverse side)

API Number 15-007-22,177-0000

OPERATOR: License # 5020
Name Rine Exploration Company
Address Suite #645, 300 W. Douglas
City/State/Zip Wichita, KS 67202
Contact Person M. Bradford Rine
Phone 316/262-5418

C SE 1/4 SE 1/4 Sec. 32 Twp. 31 S, Rg. 11
660 Ft. from South Line of Section
660 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 660 feet
County Barber

CONTRACTOR: License # 5929
Name Duke Drilling Company
City/State Wichita, KS 67202

Lease Name Cooper Well # 1-32
Ground surface elevation 1569 (L&S) feet MSL

Well Drilled For: Well Class: Type Equipment:
Oil Storage Infield Mud Rotary
X Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 50'
Depth to bottom of usable water 200'

If OWWO: old well info as follows:

Surface pipe by Alternate: 1 X 2

Operator
Well Name
Comp Date Old Total Depth

Surface pipe planned to be set 225'
Conductor pipe required -0-
Projected Total Depth 4500 feet

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 02/05/88 Signature of Operator or Agent M. Bradford Rine Title President / Geologist

For KCC Use:

Conductor Pipe Required 8-8-88 feet; Minimum Surface Pipe Required 220 feet per Alt. 1 X
This Authorization Expires 8-8-88 Approved By P.H. 2-8-88

EFFECTIVE DATE: 2-13-88

Formation Mississippian

SPUD 2-15-88

85 7/8" 225'

msw

C SE 1/4 SE 1/4 Sec. 32 Twp. 31 S, Rg. 11 East West X

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. B/Anhydrite 360'	or formation with 50 sacks	feet of. 60-40 poz, 2% gel, 3% cc
2nd plug @ ft. deep. 40' - 0'	or formation with 40 sacks	feet of. " " " "
3rd plug @ ft. deep.	or formation with 10 sacks	feet of. " " " "
4th plug @ ft. deep.	or formation with	feet of.
5th plug @ ft. deep.	or formation with	feet of.

(2) Rathole to surface minus 5 feet - 10 sacks

(b) Mousehole to surface minus 5 feet - 10 sacks

PUSHER John
TD 4450' FORMATION Miss
SURFACE PIPE 8 5/8" @ 261'
ANHYDRITE 820' ELEVATION 1569
STARTING TIME & DATE 9:10 PM
COMPLETION TIME & DATE 10:30 PM 2-23-88
1st PLUG @ 840 FT. W/ 50 SX
2nd PLUG @ 280 FT. W/ 40 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
~~MOUSE HOLE CIRCULATED W/ SX~~
~~WATER WELL PLUGGED W/ SX~~
CEMENT COMPANY B.S.T.
TECHNICIAN
60/40 670
2-24-88