

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007 -21,744 -0000
130' E of C
NE NW , Sec. 36, T 31 S, R 11 W
 feet from N/S section line
 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Chapin Well # 3-36

Operator: Hummon Corporation
Name & 400 One Main Place,
Address Wichita, KS 67202

County Barber

Well Total Depth 3930 feet 127.73

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address 107 W. Fowler, Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1:30 pm Day: 9 Month: May Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2 set at 3853' Perfs 3736' to 3731'

1st plug sand back to 3680 and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel 1 sack

hulls and release 8 5/8" rubber plug and pump an additional 125 sx cement

Maximum pressure 500# and shut in pressure 500#

Signed J. A. [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:15 pm Day: 9 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 3853' Perfs 3736' to 3731'

1st plug sand back to 3680' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel 1 sack

hulls and release 8 5/8" rubber plug and pump an additional 125 sx cement.

Maximum pressure 500# and shut in pressure 500#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun

They recovered 3082' of 5 1/2" casing.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 1984
5-18-84
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

INVOICED

DATE 5-21-84
INV. NO. 1374
5-7

Signed J. A. [Signature]
(TECHNICIAN)