

1010155

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C SW SE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,923-0000
660 feet from ~~XXX~~ SE Corner of
1980 feet from ~~XXX~~ SE Corner of
section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Chapin Well # 5-36

Operator: Hummon Corporation
Name & Address 400 One Main Place
Wichita, KS 67202

County Barber 124.64

Well Total Depth 3835 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Big-H Drilling, Inc. License Number 5148

Address 400 One Main Place, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 23 Month: September Year: 19 84

Plugging proposal received from Jerry Tharp

(company name) Big-H (phone) 316-263-8521

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 850' with 50 sx cement

2nd plug at 245' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Ken Beakey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 3:00 pm Day: 23 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement, 2nd plug at 245' with 50 sx
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate
mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun
(if additional description is necessary, use BACK of this form.)

INVOICED

(if not) observe this plugging.

DATE 10-3-84

Signed Kenneth Beakey SW
(TECHNICIAN)

INV. NO. 4002