

15-135-20713-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1973
02-21-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mull Drilling Company
Complete Address 415 Page Court Wichita, Kansas
Lease Name Goodman "A" Well No. 1
Location C SE SE Sec. 15 Twp. 20 Rge. (E) (W) 26
County Ness Total Depth 4505'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX
Other well as hereafter indicated _____
Plugging Contractor Rains & Williamson Oil
Address Wichita, Kansas License No. _____
Operation Completed: Hour 3 P Day 19 Month 2 Year 1973

The above well was plugged as follows:

RTD 4505' 8 5/8 csg set at 246' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 575' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 250' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/4 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 2/22/73
INV. NO. 7015-W