

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
07-16-1979  
JUL 16 1979  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135 - 71434 - 00-009 of this well)

Operator's Full Name PICKRELL DRILLING COMPANY  
Complete Address 205 LITWIN BUILDING - 110 NORTH MARKET - WICHITA, KANS.  
Lease Name BETZ "I" Well No. #. 1  
Location Opp. NE - SW - SE Sec. 1 Twp. 20<sup>5</sup> Rge. 26 (E) W (W) W  
County NESS Total Depth 4586 <sup>FE.</sup>  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor HELSO CASING PULLING  
Address BOX 176 CHASE, KANS. 67524 License No. 683  
Operation Completed: Hour 11:50 AM Day 13<sup>th</sup> Month JULY Year 1979

The above well was plugged as follows:

8 3/8" 220<sup>FE.</sup> J.O. CUC. 150<sup>ST</sup> - 4 1/2" - 4581<sup>FE.</sup> CUC. 100<sup>ST</sup> POZMIX T  
50<sup>ST</sup> COMMON - PERF. 4516<sup>FE.</sup> TO 4526<sup>FE.</sup> - BOTTOM SANDED  
TO 4480<sup>FE.</sup> AND 4<sup>ST</sup> CMT. - SHOT PIPE AT 2581<sup>FE.</sup> & 2583<sup>FE.</sup>  
RECOVERED 2583<sup>FE.</sup>

ORDERED 140<sup>ST</sup> 50<sup>ST</sup> POZMIX 6% GEL - 15<sup>ST</sup> GEL - 4<sup>ST</sup> HULL'S - 8 5/8" PLUG.

(PUMPED IN WITH PUMP TRUCK.)

PAT. IN. - 2<sup>ST</sup> HULL'S - 10<sup>ST</sup> GEL. - 10<sup>ST</sup> CMT. - 5<sup>ST</sup> GEL. - 2<sup>ST</sup> HULL'S - RELEASED  
PLUG. - AND 10<sup>ST</sup> CMT. - MAX PRESSURE 400<sup>PSI</sup> - CEMENTED BY ALLIED CEMENTING

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Merid Schmidt  
Well Plugging Supervisor

DATE 7-16-79

INV. NO. 0019.W