

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1964
2-6-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, Kansas

Lease Name Swartz "D" Well No. # 2

Location C SE NE Sec. 31 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 3623

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 342, El Dorado, Kansas License No. 547

Operation Completed: Hour 1:00PM Day 4th Month Feb. Year 1964

The Above well was plugged as follows:

174' of 9 5/8" surface pipe, cemented with 150 sacks. 3493' of 7" long
string, cemented with 150 sacks. Plug back to 3480'. Top perforation
3356'. Bottom of hole was sanded to 3350', and cemented with 6 sacks.
Hole was bailed down to 240', Plug was set at 240', with 10' rock bridge,
and cemented with 50 sacks, bringing the cement to 160' in the surface
pipe. Hole was filled with mud to 40', 10' rock bridge, and cemented
with 12 sacks to base cellar.
2550' of 7" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/6/64

INV. NO. 8589-4