

16 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

JAN 31 1964
1-31-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aylward Drilling Co.

Complete Address: 909 1st National Bank Bldg., Wichita, Kansas

Lease Name Warren Mortgage Co. Well No. # 2

Location C SE NW Sec. 31 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 3720

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 342, El Dorado, Kansas License No. 547

Operation Completed: Hour 5:00PM Day 30th Month Jan. Year 1964

The Above well was plugged as follows:

169' of 9 5/8" surface pipe, cemented with 150 sacks. 3458' of 7" long
string, cemented with 150 sacks. Top perforation 3295'. Bottom of hole
was sanded to 3290', and cemented with 5 sacks. Fluid level in hole
was at 225', plug and 10' rock bridge was set at 225', cemented with
40 sacks, bringing the cement to 150' in the surface pipe. Hole was
filled with mud to 40', 10' rock bridge, and cemented with 12 sacks
to base cellar.

2500' of 7" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/31/64
INV. NO. 8558-W