

14 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
DEC 19 1966  
12-19-66  
CONSERVATION DIVISION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Bowers Drilling Company, Inc.

Complete Address: 1434 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Axline "B" Well No. # 1

Location C SE NW Sec. 8 Twp. 31 Rge. 11 (E) (W) W

County Barber County Total Depth 4472'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X     

Other well as hereafter indicated:     

Plugging Contractor: Bowers Drilling Company, Inc.

Address: 1434 Wichita Plaza Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 12:00AM Day 18th Month Dec. Year 1966

The Above well was plugged as follows:

290' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole was  
filled with drilling mud to 290', 1st cementing plug, bridged with 1 sack  
of Gel-Mud, and 1/2 sack of hulls on fluid at 290', and cemented with 35  
sacks. Hole was filled with drilling mud to 40', 2nd cementing plug,  
bridged with 1 sack of Gel-Mud, and 1/2 sack of hulls on fluid at 40', and  
cemented with 10 sacks to the base of the cellar. Rat hole was cemented  
with 5 sacks. This cementing was done by Globe Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving  
Well Plugging Supervisor

DATE 12/19/66  
INV. NO. 4494-w