

*14*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

MAY 7 1964  
*5-7-64*  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Lario Oil & Gas Company

Complete Address: 301 S. Market, Wichita, Kansas

Lease Name Axline "A" Well No. # 1

Location SW NW SE Sec. 8 Twp. 31 Rge. 11 (E) (W) W

County Barber Total Depth 3783

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Glen & Smith Casing Pulling Co.

Address: 204 East Sixth, Ellinwood, Kansas License No. 396

Operation Completed: Hour 3:30PM Day 1st Month May Year 1964

The Above well was plugged as follows:

325' of 8 5/8" surface pipe, cemented with 250 sacks. 3783' of 5 1/2" long  
string, cemented with 100 sacks. Plug back to 3732'. Top perforation  
3720'. Bottom of the hole was sanded to 3700', and cemented with 5  
sacks. Fluid in hole was bailed down to 300'. Plug was set at 300',  
with 10' of rock bridge, and cemented with 25 sacks. Hole was filled  
with mud to 40', with 10' of rock bridge, and cemented with 10 sacks  
to base of cellar.

3222' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 5/8/64

INV. NO. 9110-W