

KANSAS

4
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
12-7-70
DEC 7 - 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leben Drilling Inc.

Complete Address Box 486 Great Bend, Ks

Lease Name Glenn Oldfather Well No. 3

Location NW/SW/SE Sec. 7 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4580

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Ks License No. 462

Operation Completed: Hour 5:00 PM Day 4 Month 12 Year 1970

The above well was plugged as follows:

132 ft of 16" surface pipe cemented with 125 sacks. 703 ft of 103/4
cemented with 250 sacks. 4580 ft of 5 1/2 long string cemented with 400
sacks. Top perf. 4437 ft. Set plug at 4440 ft. Sand back to 4400 ft.
5 sacks cement with bailer. Pulled 2422 ft of 5 1/2. Set 10 ft rock b
ridge at 220 ft. Fill hole with 5 yds of redimix to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *J. Russell B. Hunter*
Well Plugging Supervisor

DATE 12/7/70
INV. NO. 2988-W