

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
6-21-71  
JUN 21 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Leben Oil Co.

Complete Address Box 486 Great Bend, Ks 67530

Lease Name Oldfather Well No. 1

Location C SE Sec. 7 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4561

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Forbes Casing Pulling Inc.

Address Box 221 Great Bend, Ks License No. 637

Operation Completed: Hour 11:00 AM Day 17 Month 6 Year 1971

The above well was plugged as follows:

35 ft 15" surface pipe cemented, circulated. 56 ft 103/4 surface pipe  
cemented, circulated. 720 ft 8 5/8 surface pipe cemented, circulated.  
4554 ft 5 1/2 long string cemented with 200 sacks. Top perf. 4435 ft.  
Sand back to 4420 ft., 5 sacks cement with bailer. Pulled 2830 ft  
5 1/2. Set 10 ft rock bridge at 350 ft. Fill hole with 8 yds redimix.  
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: J. Russell Bilonsten  
Well Plugging Supervisor

INVOICED

DATE 6/22/71  
INV. NO. 3889-W