

15-165-20573-00-00

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
MAR 01 1976
03-01-1976
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Frontier Oil Co.

Complete Address 1720 Wichita Plaza, Wichita, Kansas

Lease Name Shank "B" Well No. 1

Location NE NE SW Sec. 36 Twp. 16 Rge. (E) (W)17

County Rush Total Depth 3610'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4:15 A Day 27 Month 2 Year 1976

The above well was plugged as follows:

RTD 3610' 8 5/8 csg set 249' cwc 170 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 450' thru drill pipe.

Heavy mud to 250' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Len Massey
Well Plugging Supervisor

DATE 3-2-76

INV. NO. 2832-W