

15-165-30096-00-00

~~KANSAS~~

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

11-18-1974
RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name John O. Farmer, Inc.

Complete Address P. O. Box 352 Russell, Kansas 67665

Lease Name Usher Well No. 1

Location NE NE NW Sec. 31 Twp. 16 Rge. (E) (W) 17

County Rush Total Depth 3626'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co Tools

Address License No.

Operation Completed: Hour 1 P Day 11 Month 11 Year 1974

The above well was plugged as follows:

Total Depth 3626' 2 1/2" tbg set at 3218' cw 125 sk. 8 5/8 csg 249' cwc 150 sk.

2 1/2" tbg perf. 3058-3068)

Pumped down 2 1/2" tbg with 40 sk cmt. Top of cem. 2755'.

Recovered 560'. of tbg.

Set 40 sk cmt plug at 560' thru tbg.

set 40 sk cmt plug at 355' thru tbg.

Set 30 sk cmt plug at 204' thru tbg.

Set 20 sk cmt plug 65' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/18/74

INV. NO. 310-W

Signed: Leo Massey
Well Plugging Supervisor

