

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

05-20-1974
80153

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-165-20026-00-01 (of this well)

Operator's Full Name Craig Parker

Complete Address 2712 Hickory, Hays, Kansas 67601

Lease Name Urban (OWWO) Well No. 1

Location NE NE SE Sec. 24 Twp. 16 Rge. (E) (W) 17

County Rush Total Depth 3507'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Dreiling Oil

Address Route #2, Victoria, Kansas License No. 730

Operation Completed: Hour 11 A Day 19 Month 5 Year 1976

The above well was plugged as follows:

Total Depth 3507' 8 5/8 csg set 212' cwc

4 1/2 csg set 3507' cw 150 sk cem.

4 1/2 csg Perf. (3407'-3411')

Filled 4 1/2 csg with sd (3507-3400) dumped 5 sk cem W/dump bailer. (3400-3365)

Cutoff & recovered A/2300' of 4 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs

hulls, released 8 5/8 plug & 130 sk 50-50 poz 6% total gel & shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5/27/76

INV. NO. 32.61-W