

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 165-20,707-00-00 (of this well)

Operator's Full Name Energy Oil, Inc.

Complete Address 4469 E. Hwy #34 Loveland, Co.

Lease Name Urban Well No. 4

Location E/2 E/2 SE Sec. 24 Twp. 16 Rge. (E) (W) 17

County Rush Total Depth 3590'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Western Petro.

Address Colby, Ks. License No.       

Operation Completed: Hour 5:30 P Day 24 Month 2 Year 1979

The above well was plugged as follows:

RTD 3590' 8 5/8 csg set 262' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 420' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 27 1979  
02-27-1979  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: [Signature]  
Well Plugging Supervisor

DATE 2-28-79

INV. NO. 9196.W