

15-101-20015 0000

Form CP-3  
Rev. 6-4-68

KANSAS

*SP*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling & Petroleum Resources,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Foster Well No. C-1

Location NE-SE-NE Sec. 34 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4577'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Dunne-Gardner Petroleum, Incorporated,

Address 200 West Douglas, Wichita, Kansas. License No.       

Operation Completed: Hour 2:30 PM Day 22 Month 7 Year 1971

The above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 225 Sx.  
top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru  
DP from 975' to 650'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dickel*  
Well Plugging Supervisor

INVOICED

DATE 7-29-71  
INV. NO. 4059-W