

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

06-21-1974

API Number 15-115-20571 0000 (of this well)

Operator's Full Name Frontier Oil Company

Complete Address 1720 Kansas State Bank Bldg., Wichita, Kansas 67202

Lease Name Jacobs "A" Well No. 1

Location SE SE NW Sec. 8 Twp. 16 Rge. (E) (W) 17

County Rush Total Depth 3570'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 1 P Day 19 Month 6 Year 1976

The above well was plugged as follows:

Total Depth 3570' 8 5/8 csg set 243' cwc 150 sx.

4 1/2 csg set 3568' cw 150 sx cem. with top perf. (3171) FBTD 3330'

Set 4 1/2" wood plug at 3000' -poured 10' sd- dumped 3 sx cem. W/dump bailer. (3000-2950)

Cutoff & recovered 2600' of 4 1/2 csg.

Allied Cementing Co. squeezed 8 5/8 csg with 20 sk gel & water W/300 lbs hulls,

released plug & 120 sx 50-50 poz 6%. PP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 6/21/76

INV. NO. 3381-W