

15-165-00087-00-01

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

NOV 8 1973  
11-08-1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Frontier Oil Company  
Complete Address 1720 Wichita Plaza, Wichita, Kansas 67202  
Lease Name Burgardt "A" Well No. 1  
Location SW SW NE Sec. 15 Twp. 16 Rge. (E) (W) 17  
County Rush Total Depth 3574'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling Co.  
Address Box 405 Chase, Kansas 67524 License No. 436  
Operation Completed: Hour 10:30 A Day 6 Month 11 Year 1973

The above well was plugged as follows:

Total Depth 3574' 8 5/8 csg set at 293' cwe  
5 1/2 csg set at 3520' cw 275 sk cem. & perf. (2712-2732)  
Set 4 1/2 wood plug at 2675' - poured 25' sd & dumped 2 sk cem W/dump bailer. (2625-2675)  
Cutoff and recovered 600' of 4 1/2 csg.  
Pumped down 8 5/8 csg with 10 sk gel & water W/300 lbs hulls -- released 8 5/8 plug  
and pumped 120 sk 50-50 poz cem. W/2% total gel. Max. PP 800# SIP 350 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Mansur  
Well Plugging Supervisor

11/9/73  
INV. NO. 8142-10