

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1974
CONSERVATION DIVISION
Wichita, Kansas

02-06-1974

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Frontier Oil Company
Complete Address 1720 Wichita Plaza Bldg., Wichita, Kansas 67202
Lease Name Burgardt "A" Well No. 6
Location NE SW NE Sec. 15 Twp. 16 Rge. (E) (W) 17
County Rush Total Depth 3585'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling., Inc.
Address Bex 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 10:30 A Day 2 Month 2 Year 1974

The above well was plugged as follows:

- Total Depth 3585' 8 5/8 csg set at 1151' ewc 425 sk.
- 5 1/2 csg set at 3584' cw 120 sk cmt.
- 5 1/2 csg perf. (3470')
- Filled 5 1/2 csg with sand (3450-3585) dumped 5 sk cmt W/dump bailer. (3415-3450)
- Cutoff and recovered 2500' of 5 1/2 csg.
- Filled 3 5/8 csg with mud to 375' -set rock & sand bridge (3750-350')
- Dumped readymix cement from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Masney
Well Plugging Supervisor

INVOICED

DATE 2/8/74
INV. NO. 8534-W