

15-165-01638-00-02

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - OWWO (of this well)

MAY 23 1978
05-23-1978

Operator's Full Name N - B Oil Co., Inc.

Complete Address Box 506, Russell, Kansas 67665

Lease Name Urban (OWWO) Well No. 1

Location SE SE SW Sec. 16 Twp. 16 Rge. (E) (W) 17

County Rush Total Depth 3571'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 2 P Day 22 Month 5 Year 1978

The above well was plugged as follows:

Total Depth 3571' 8 5/8 csg set 1140' cwc

4 1/2 csg set 3471' cw 100 sk cem.

4 1/2 csg PBTD 3445' with top perf. (2948')

Filled 4 1/2 csg with sand (3445'-2900') dumped 3 sk cem W/dump bailer. (2900'@2870')

Cutoff & recovered A/2500' of 4 1/2 csg.

Filled 8 5/8 csg with mud to 450' -set rock & sand bridge (450'-420')

Filled with readymix cement from 420' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-23-78
INV. NO. 7353 W

Signed: Bob Murray
Well Plugging Supervisor