


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-101-00001-00000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Lane _____ County. Sec. 9 Twp. 20 Rge. 27 (E) W (W)
Location as "NE/CNW&SW¼" or footage from lines 3300' S. & 4620' W. of NE Cor.
Lease Owner Cities Service Oil Company
Lease Name Lewis "C" Well No. 1
Office Address Box 144, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 3 19 60
Application for plugging filed December 3 19 60
Application for plugging approved December 3 19 60
Plugging commenced December 3 19 60
Plugging completed December 3 19 60
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker
Producing formation None Depth to top - Bottom - Total Depth of Well 5100 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13-3/8"	412'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

5100-600', mud.

600-400', Halliburton plug, 20 sacks cement, mud.

400' to base of cellar, Halliburton plug, 20 sacks cement, mud, 20 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Bros., Inc.
Address Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

John D. Forsyth (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 144, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 19 60

My commission expires March 12, 1963.

Notary Public.

WELL RECORD

WILDCAT.....

DISCOVERY.....

15-10/0000 7-0000

POOL.....

COMPANY Cities Service Oil Co. WELL # 1 FARM Lewis "C"

LOCATION 3000' South and 4620' West of NE Corner

Section 9, Township 20, Range 27W.

ELEV. 2722 R.B., 2719 D.F. 2714 Gr. CO. Lane STATE Kansas

IP. Dry hole. P. and A. 12-4-60.

PERFS.

FRAC. ACID None

T.D. 5100' PBTD. GRAV/GOR.

DRLG. COMM. 11-9-60 COMP. 12-3-60 CONTRACTOR Peel Bros., Inc.

CASING RECORD:

13-3/8" at 412' with 450 sacks cement.

FORMATION RECORD:

shale	0-495
shale and shells	2012
Anhydrite	2045
shale and shells	2055
shale and lime	2230
shale	2310
broken lime and shale streaks	2470
shale and lime	2725
broken lime	2765
shale and lime	2840
lime and shale	2880
shale and lime	2975
lime	3125
shale and lime	3220
lime and shale streaks	3295
lime	3350
shale and lime	3440
lime and shale	3570
shale and lime	3695
lime	4883
lime and shale	4925
lime	5100 T.D.

Slope Tests (Syfo):

1000'	- 1°
1500'	- 0°
2000'	- 1/4°
2500'	- 1/4°
3000'	- 1/4°
3500'	- 1/4°

PRODUCED
BY PEEL BROS.