

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

15-101-20481-0000

Give All Information Completely
Make Required Affidavit

COUNTY Lane SEC. 15 TWP. 20S RGE. 27W E/W
Location as in quarters or footage from lines:
 C SW SW

●			

Locate Well
correctly on above
Section Platt.

Lease Owner Argonaut Energy Corporation
Lease Name Brown A Well No. 1
Office Address Box 4060 Amarillo, Texas 79116-4060
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 2/20/81
Application for plugging filed 9-6-83
Plugging commenced 9-30-83
Plugging completed 10-3-83
Reason for abandonment of well or producing formation Production ceased to be commercial.
Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation Cherokee Depth to top 4484' bottom 4500' T.D. 4510
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	299	none
				4 1/2	4510	2408

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pump 20 sks. of cement @ 4500 to 4250
Pump 50 sks. of cement @ 349 to 249
Put 10 sks. of cement @ 40 to 0
Cut off & cap 8 5/8 3" below ground level

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Box 506 Liberal, Kansas 67901

STATE OF Texas COUNTY OF Potter, ss.
Billy D. Johnson, ARGONAUT ENERGY CORP (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Billy D. Johnson
P. O. BOX 4060, Amarillo, Texas
(Address) 79116-4060

SUBSCRIBED AND SWORN TO before me this 17th day of October, 1983
LOIS B. YATES
Notary Public, State of Texas
My Commission Expires, July 27, 1985
My Commission expires: 7/27/83
Lois B. Yates
Notary Public.



RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1983
CONSERVATION DIVISION
Wichita, Kansas

WF

15-101-20481-0000

WELL LOG

A BROWN # 1
CSWSW 15-205-27W
Lane County, Kansas

Name of Operator: Argonaut Energy
P.O. Box 4060
Amarillo, Texas 79106


Date Completed: September 17, 1980

<u>FROM</u>	<u>TO</u>	
0	339	Shale
339	1125	Shale & Red Bed
1125	1977	Shale & Sand
1977	2145	Shale
2145	2490	Shale & Lime
2490	2975	Shale
2975	3880	Shale & Lime
3880	4015	Lime
4015	4245	Lime & Shale
4245	4510	Lime
4510		T.D.

STATE OF KANSAS

COUNTY OF BARTON ss


George E. Miller, Jr., President of Blue Goose Drilling Co., Inc.,
being first duly sworn on oath says: That I have knowledge of the facts,
statements and matters herein contained and the log of the above described
well as filed and that the same are true and correct.


George E. Miller, Jr.

Subscribed and sworn before me this 24th day of September, 1980.


Notary Public

My Commission expires: 8-1-81



RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1981

CONSERVATION DIVISION
Wichita, Kansas