

STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 101-21,117-K00-01

LEASE NAME Thomas (Brown)

WELL NUMBER 1

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 15 TWP. 20S RGE. 27W (X) or (W)

COUNTY Lane

Date Well Completed 9/23/88

Plugging Commenced 2/17/03

Plugging Completed 2/17/03

RECEIVED  
2-20-03  
FEB 20 2003

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

KCC WICHITA

LEASE OPERATOR WHITETAIL CRUDE, INC

ADDRESS P O Box 544, Ness City, KS 67560-0544

PHONE (785) 798-3641 OPERATORS LICENSE NO. 31627

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/14/03 (date)

by Mike Maier (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippian Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size 4 1/2"	Put In 4568'	Pulled out 300'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from    feet to    feet each side.  
2/15/03 Sanded perfs off to 4100' & capped sand plug w/2 sks cement thru dump bailer.  
2/17/03 Spotted a 50 sk plug 60/40 3% CC thru tubing @ 1200'. Pulled tubing out, shot casing off @ 500' and tried to pump into. Could not pump. Moved up and shot casing off @ 300'. Pulled 300' of 4 1/2" casing out and filled 8 5/8" with cement to surface. Job complete.

Name of Plugging Contractor Swift Service, Inc License No. \_\_\_\_\_


Address P O Box 466, Ness City, KS 67560-0466

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Whitetail Crude, Inc

STATE OF Kansas COUNTY OF Ness, ss.

Mike J. Fritzler, President of Whitetail Crude, Inc (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike J. Fritzler  
(Address) P O Box 544, Ness City, KS 67560-0544



SUBSCRIBED AND SWORN TO before me this 18th day of February, 2002, xx

Debra Kerr  
Notary Public Debra Kerr

My Commission Expires: 4/20/05

USE ONLY ONE SIDE OF EACH FORM