

15-101-20458-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Lane SEC. 16 TWP. 20 RGE. 27W E/W
 Location as in quarters or footage from lines:
C SE SE

			●

Locate Well
 correctly on above
 Section Platt.

Lease Owner Argonaut Energy Corporation
 Lease Name Witt"B" Well No. 1
 Office Address Box 4060 Amarillo, Texas 79116-4060
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed 9/29/80
 Application for plugging filed 9-6-83
 Plugging commenced 9-27-83
 Plugging completed 9-27-83
 Reason for abandonment of well or producing formation Production Ceased to be Commercial.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
 Producing formation Mississippian Depth to top 4510' bottom 4526' T.D. 4994
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	292	none
				4 1/2	4992	1932

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set.

Pump 29 sks. of cement @ 4526 to 4310
 Pump 60 sks. of cement @ 342 to 242
 Put 15 sks. of cement @ 40 to 0
 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sarrents Casing Pulling Service Box 506 Liberal, Kansas 67901

STATE OF TEXAS COUNTY OF POTTER, ss.
Billy D. Johnson, ARGONAUT ENERGY CORP (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Billy D. Johnson
P. O. BOX 4060, Amarillo, Texas
 (Address) 79116-4060



SUBSCRIBED AND SWORN TO before me this 17th day of October, 19 83
 LOIS B. YATES
 Notary Public, State of Texas
 My Commission Expires, July 27, 1985

My Commission expires: 7/27/85

RECEIVED
 STATE CORPORATION COMMISSION
 Lois B. Yates
 Notary Public.
 OCT 19 1983
 10-19-83
 CONSERVATION DIVISION
 Wichita, Kansas

15-101-20458-0000

WELL LOG

Witt B #1
C SE SE Sec. 16-20S-27W
Lane County, KS

Name of Operator: Argonaut Energy Corporation
2209 West 7th Street, Suite 200
P. O. Box 4060
Amarillo, TX 79106

Date Completed: 7-10-80

<u>FROM</u>	<u>TO</u>	
0	642	Shale and Red Bed
642	1942	Shale
1942	3405	Shale and Lime
3405	4618	Lime
4618	4994	Lime and Chert
4994		Total Depth

STATE OF KANSAS


COUNTY OF BARTON ss

George E. Miller, Jr., President of Blue Goose Drilling Co., Inc.,
being first duly sworn on oath says: That I have knowledge of the facts,
statements and matters herein contained and the log of the above described
well as filed and that the same are true and correct.

George E. Miller, Jr.
George E. Miller, Jr.

Subscribed and sworn before me this 21st day of July, 1980.

Margaret Schwamborn
Notary Public



RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1980

CONSERVATION DIVISION
Wichita, Kansas