


15101205170000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Lane _____ County, Sec. 20 Twp. 20S Rge. _____ (E) 27W (W)
Location as "NE/CNW&SW¼" or footage from lines NW NE SW
Lease Owner Chief Drilling Co., Inc.
Lease Name Kline Well No. 1
Office Address 905 Century Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 3-4-81 19____
Application for plugging filed 3-4-81 19____
Application for plugging approved 3-4-81 19____
Plugging commenced 3-4-81 19____
Plugging completed 3-4-81 19____
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4535' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	302'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged w/60 sx. @ 600', 30 sx. @ 280', 10 sx. @ 40', & 5 sx. in rathole

4-24-81

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Warrior Drilling, Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
F. W. Shelton, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. W. Shelton, Jr.
905 Century Plaza, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of March, 1981

Marilyn Lahar
Marilyn Lahar Notary Public.

My commission expires _____
Marilyn Lahar
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXP. 4-30-83

WELL LOG

15101-20517-0000

CHIEF DRILLING CO., INC.
905 Century Plaza
Wichita, Kansas 67202

#1 KLINE
NW NE SW Sec. 20-20S-27W
Lane County, Kansas

CONTRACTOR: Warrior Drilling, Inc.
CASING RECORD: 8 5/8" @ 302' w/185 sx.

COMMENCED: Feb. 23, 1981
COMPLETED: March 4, 1981

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATIONS</u>
Surface Sand & Clay	0	307	2604 Gr.
Sand & Shale	307	794	2606 D.F.
Shale & Sand	794	1400	2609 K.B.
Sand & Shale	1400	1717	
Shale	1717	1898	
Anhydrite	1898	1935	
Shale	1935	4056	
Shale & Lime	4056	4285	
Lime	4285	4535	
RTD	4535		

D & A

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW NE SW of Sec. 20-20S-27W, Lane County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.


F. W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 9th day of March, 1981.



Marilyn Lahar Notary Public