

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-101-20 262-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Lane \_\_\_\_\_ County. Sec. 22 Twp. 20 Rge. 27 E/W  
Location as "NE/CNW, SW 1/4" or footage from lines  
100' E & 100' S of SW NW

Lease Owner Jack Bowles  
Lease Name Burnett Well No. I  
Office Address 101 Park Avenue, Oklahoma City, Oklahoma  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed 11/24/77 19  
Application for plugging filed 11/24/77 19  
Application for plugging approved 11/24/77 19  
Plugging commenced 11/24/77 19  
Plugging completed 11/24/77 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4600  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	367	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

RECEIVED

STATE CORPORATION COMMISSION

DEC - 8 1977  
12-8-77  
CONSERVATION DIVISION  
Wichita, Kansas

Bottom Plug at 550' with 70 sacks 50/50 Poz, 6% Gel  
Middle Plug at 300' with 20 sacks 50/50 Poz 6% gel  
Top & bridge at 40' with 10 sacks 50/50 Poz 6% gel  
2 sacks in rathole  
Job complete 1P.M. 11/24/77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bill Rowe  
Slawson Drilling Company, 200 Douglas Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
James C. Remsberg (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg  
James C. Remsberg  
200 Douglas Building, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 6 day of December, 1977

Mary Lou Taylor  
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

OPERATOR: Jack Bowles  
Suite 1230  
100 Park Avenue  
Oklahoma City, Oklahoma 73102

LEASE: Burnett No.1  
100' E & 100' S of SW NW  
Sec. 22-20S-27W  
Lane County, Kansas

15-101-20262-0000

CONTRACTOR: Slawson Drilling Company, Inc.  
200 Douglas Building  
Wichita, Kansas 67202

COMMENCED: 11/16/77

COMPLETED: 11/24/77

RTD: 4600'

CASING: 8-5/8" set at 367' with 250 sx cement

0' to 370' 12 1/4" Surface Hole Post Rock, Clay & Shale  
370' to 1410' Shale & Shells  
1410' to 1615' Sand  
1615' to 1900' Shale  
1900' to 1939' Anhydrite  
1939' to 2512' Shale & Shells  
2512' to 2540' Shale & Lime  
2540' to 3920' Lime & Shale  
3920' to 4495' Lime  
4495' to 4525' Lime & Shale  
4525' to 4600' Lime  
4600' RTD

RECEIVED  
STATE CORPORATION COMMISSION  
DEC - 8 1977  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.  
hereby state that the above and foregoing is a true and accurate copy of the  
Burnett No. 1 well for Jack Bowles.

*James C. Remsberg*  
James C. Remsberg

Subscribed and sworn to me this 6th day of December 1977

*Mary Lou Taylor*  
Mary Lou Taylor, Notary

My commission expires January 17, 1981

