

15107-20006-0000

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 26 1970  
10-26-70  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company, Incorporated,  
Complete Address 1625 Wichita Plaza, Wichita, Kansas.  
Lease Name Cramer Well No. 1  
Location CSW-NE Sec. 20 Twp. 18 Rge. (E) (W) 30  
County Lane Total Depth 4655'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Rains & Williamson Oil Company, Incorporated,  
Address 1625 Wichita, Plaza, Wichita, Ks. License No.         
Operation Completed: Hour 8:00 AM Day 20 Month 10 Year 1970

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 180 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru  
DP from 975' to 650'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. D. Scholtz

Well Plugging Supervisor

DATE 10/26/70

INV. NO. 2749-W