

15-101-20039-0000

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

1972
9-11-72
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company & Mull Drilling Company,
Complete Address 617 Union Center, Wichita, Kansas.
Lease Name Steele-Whiteman Well No. 1
Location CNE-SW Sec. 21 Twp. 18 Rge. (E) (W) 30
County Lane Total Depth 3323'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Murfin Drilling Company,
Address 617 Union Center, Wichita, Kansas. License No.
Operation Completed: Hour 3:15 AM Day 8 Month 9 Year 1972

The above well was plugged as follows:

239'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 110 Cu. Ft. cement
thru DP from 1075' to 750'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 9/12/72
INV. NO. 0305-40