



State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS
JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1962

CONSERVATION DIVISION
Wichita, Kansas

*****Ogden, Director*****

500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date June 10, 19 62, authorized the following
plugging operation:

Operator's Full Name: Dick Hess

Complete Address: McPherson, Kansas

Lease Name: Karber Well No. 1

Location: NW SW SW Sec. 29 Twp. 16 Rge. 1 (E) (W)X
ANB REC

County: Saline Total Depth: 2708'

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 125' with heavy mud.

Push plug and 1/4 sack hulls to 125'. Cement with 20 sacks thru
drill pipe. Fill hole with mud to 25'. Push plug and 1/4 sack hulls
to 25' and cement to bottom of cellar with 8 sacks.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 6/15/62
INV. NO. 5186-W