

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-19112-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 27-21S-19E  
554 feet from S Section Line, 1006 feet from E Section Line  
Lease/Unit Name: KATTENHORN SOUTH Well Number: 21  
County: ANDERSON Total Vertical Depth: 861 feet

Operator License No.: 9362

Conductor Pipe: Size feet:

Op Name: WILLIAMS GAS PIPELINE CENTRAL, IN

Surface Casing: Size 8 feet: 15

Address: 13430 W 98TH STREET  
SHAWNEE MISSION, KS 66215

Production: Size 4 feet: 861

Liner: Size feet:

25 SX CMT \$35.00

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/22/2001 2:30 PM

Plug Co. License No.: 6372

Plug Co. Name: SPLANE PULLING & ROUST SVS, INC.

Proposal Rcvd. from: BERNIE ROCKERS

Company: WILLIAMS GAS PIPELINE

Phone: (785) 448-4816

Proposed Plugging Method: WASH DOWN TO TD & FILL WELL WITH CEMENT TO SURFACE. CUT & CAP 3" BELOW SURFACE.

Plugging Proposal Received By: TOM WELSH

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/22/2001 5:00 PM

KCC Agent: TOM WELSH

Actual Plugging Report:

RAN 800' OF 1" PIPE INSIDE 4" PIPE, WELL WAS PERFORATED AT 300' AND 500'. PUMPED CEMENT TO SURFACE AND PULLED 1", TIED TO 4" PIPE AND CIRCULATED CEMENT TO SURFACE OUTSIDE 4" PIPE. TOTAL CEMENT 130 SACKS.

SEP 10 2001

RECEIVED  
KCC District #3

SEP 7 2001

Charute, KS

Remarks:

Plugged through:

District: 03

Signed

Thomas Welsh by BL  
(TECHNICIAN)

INVOICED

DATE

9-10-01

INV. NO.

2002060436