

8-29

15:10/00028'0000

369

To: 1 070581
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 Drill Completion Date 3/13/62

C SE SE, SEC. 33, T 16 S, R 27 W/4
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293

Lease Name Anderson Well # 1

Operator: Helmerich & Payne, Inc.

County Lane 152.75

Name & Address P.O. Box 558

Well Total Depth 4700 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Helmerich & Payne, Inc. License Number 5293

Address P.O. Box 558, Garden City, KS 67846

Company to plug at: Hour: 11:40 a.m. Day: 29 Month: 8 Year: 19 88

Plugging proposal received from Ken Jehlik

(company name) Helmerich & Payne, Inc. (phone) 316-276-3693

were: 5 1/2" at 4322' PBSD 4322' Perfs at 4207-18' Elevation 2697' GL DV'd at 999', cem. to 0'

1st plug pump 50 sx cement with 200 lbs. hulls through tubing at 4065',

2nd plug pump 20 sx cement through tubing at 2112',

3rd plug pump 70 sx cement at 996'.

RECEIVED
STATE CORPORATION COMMISSION
9-2-88
SEP-2 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 29 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx 60/40 Pozmix 6% gel with 200 lbs. hulls through tubing at 4065'.

2nd plug pumped 20 sx 60/40 Pozmix 6% gel through tubing at 2112', circulated hole with saltwater treated with 5 gallons of Anhib.

3rd plug pulled tubing to 996', circulated with 70 sx 60/40 Pozmix 6% gel and 50 sx 60/40 Pozmix 2% gel.

Remarks: Used 60/40 Pozmix 6% gel and 2% gel by Halliburton. No casing recovery. (If additional description is necessary, use BACK of this form.)

INVOLVED (did not observe this plugging.)

DATE 9-9-88

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 22193 8-29