

To: 1051895 2-8  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,693-0000  
SW SE NW, SEC. 18, T 19 S, R 27 W/EX  
2293 feet from N S section line  
1640 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Lease Name Maughlin Well # 1

Operator: Ritchie Exploration, Inc.

County Lane

Name & Address 125 N. Market, Ste. 1000

Well Total Depth 4643 150.90 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 213

Abandoned Oil Well Gas Well Input Well SMD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 12:30 a.m. Day: 8 Month: 2 Year: 1995

Plugging proposal received from Judy

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2067-99'  
1st plug at 2090' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,  
3rd plug at 600' with 40 sx cement, 4th plug at 240' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 2:30 a.m. Day: 8 Month: 2 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2090' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 240' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I ( ) hereby certify to observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 2-27-95

INV. NO. 422821

COMMISSION  
FEB 1 1995  
2-13-95