

11-13

1 090142

TG: STATE CORPORATION COMMISSION CONSERVATION DIVISION - PLUGGING SECTION 200 COLORADO DERBY BUILDING WICHITA, KANSAS 67202

API NUMBER 15- 101-21,606-0000 NE NW SW, SEC. 19, T. 19 S, R. 27 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9482

Operator: National Petroleum Reserves, Inc. Name & Address 250 N. Rock Rd., Suite 340 Wichita, KS 67206

2260 feet from S section line

4240 feet from E section line

Lease Name Haag Well # 1

County Lane 151.12

Well Total Depth 4650 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665

Company to plug at: Hour: 9 a.m. Day: 13 Month: 11 Year: 19 91

Plugging proposal received from Jack Fox

(company name) Emphasis Oil Operations (phone) 913-483-3516

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2061-88' 1st plug at 2090' with 50 sx cement, 2nd plug at 1160' with 80 sx cement, 3rd plug at 580' with 50 sx cement, 4th plug at 310' with 50 sx cement, 5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 a.m. Day: 13 Month: 11 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2090' with 50 sx cement,

2nd plug at 1160' with 80 sx cement,

3rd plug at 580' with 50 sx cement,

4th plug at 310' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel # floseal by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED

(if applicable) observe this plugging.

DATE 12-4-91

Signed [Signature] (TECHNICIAN)

INV. NO. 33934

RECEIVED STATE CORPORATION COMMISSION NOV 18 1991 11-18-91