

5-5

24R

To: 1 020378  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,582-0000

NW NW SW, SEC. 19, T 19 S, R 27 W/E  
2310 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Haag Well # 1-19

Operator: Chief Drilling, Inc.

County Lane 151.77

Name & Address 224 E. Douglas, Suite 530  
Wichita, KS 67202

Well Total Depth 4670 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Chief Drilling, Inc. License Number 5886

Address 224 E. Douglas, Suite 530, Wichita, KS 67202

Company to plug at: Hour: 3:30 p.m. Day: 5 Month: 5 Year: 19 91

Plugging proposal received from Marrion Burris

(company name) Chief Drilling, Inc. (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2060-93'

1st plug at 2095' with 50 sx cement, 2nd plug at 1050' with 50 sx cement,

3rd plug at 550' with 50 sx cement, 4th plug at 300' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6 p.m. Day: 5 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2095' with 50 sx cement,

2nd plug at 1050' with 50 sx cement,

3rd plug at 550' with 50 sx cement,

4th plug at 300' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 5-22-91

MIX. NO. 31863

Signed Glenn Barlow (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
5-7-91  
MAY 7 1991  
CONSERVATION DIVISION  
Wichita, Kansas