

To: 1 080123
STATE CORPORATION COMMISSION

5-21

API NUMBER 15- 101-21,742 - 0000

Wichita State Office Bldg. - PLUGGING SECTION App. E/2 NW NW, SEC. 19, T 19 S, R 27 W/8
130 S. Market, Room 2078
Wichita, KS 67202

585 feet from ~~N~~ section line
915 feet from ~~W~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5030 Lease Name Habiger Well / 1-19

Operator: Vess Oil Corporation (Landmark Expl.) County Lane 151.22

Name: Address 8100 E. 22nd St. N, Bldg. 300 Well Total Depth 4653 feet

Wichita, KS 67226 Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 305

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: Day: 21 Month: 5 Year: 1997

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2054' Elevation 2735'
1st plug at 2080' with 50 sx cement,

2nd plug at 1200' with 50 sx cement, 3rd plug at 600' with 40 sx cement,

4th plug at 340' with 50 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cmt.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 p.m. Day: 21 Month: 5 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 2080' with 50 sx cement,

2nd plug at 1200' with 50 sx cement, 3rd plug at 600' with 40 sx cement,

4th plug at 340' with 50 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

RECEIVED
KANSAS
CORPORATION
COMMISSION
MAY 29 1997

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
DATE MAY 29 1997

Signed Kevin P. Strube (TECHNICIAN)

INV. NO. 48207