

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20154-00-00
Spot: CSEWNNE Sec/Twnshp/Rge: 29-18S-30W
990 feet from N Section Line, 990 feet from E Section Line
Lease/Unit Name: COWDERY 1650 Well Number: 1
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: N HWY 283 PO BOX 544
NESS, KS 67560

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 327 WITH 175 SX CMT
Production: Size 4.5 feet: 4436 WITH 100 SX CMT 149.50
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/10/2001 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: FRITZLER TRUCKING Phone: (785) 798-3641

Proposed Plugging Method: SAND BACK TO 4200' WITH 4 SX CMT ON TOP BY DUMP BAILER. PERFORATE AT 1208'. PUMP DOWN 4 1/2" 100 SX @ 1208'. SHOOT PIPE AT 537' AND PUMP 50 SX CMT. PULL UP TO 40' & PUMP 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/10/2001 12:15 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4360'. PERFS AT 4266-86, 4302-04, 4346-48, 4363-73. CIBP @ 4360'. SANDED BACK TO 4200' WITH 4 SX CMT ON TOP BY DUMP BAILER. LOG-TECH PERFORATED AT 1208'. SWIFT PUMPED DOWN 4 1/2" 100 SX CMT AT 1208'. SHOT PIPE AT 537' AND PUMPED 50 SX CMT. PULLED UP TO 40' AND PUMPED 15 SX CMT. CMT STAYED AT SURFACE.

INVOICED

DATE 5-16-01
JV. NO. 2001061812

MAY 16 2001
5-16-01
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 537' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

MAY 14 2001

Form 20