

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20182-00-00 - 0000
Spot: CNWNWNE Sec/Twnshp/Rge: 29-18S-30W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: COWDERY Well Number: 2
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: N HWY 283 PO BOX 544
NESS, KS 67560

Conductor Pipe: Size feet: 8 1/4 9.50
Surface Casing: Size 8.625 feet: 302
Production: Size 4.5 feet: 4453 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/02/2002 10:25 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: Company: Phone:

Proposed Plugging Method: SAND TO 3240' WITH 4 SX CMT. 1ST PLUG AT 1300' WITH 80 SX CMT. 2ND PLUG AT 525' WITH 40 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 01/02/2002 1:00 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PERFS AT 4270-90, 4303-06, 4352-55, 4128-32'. SANDED TO 3240' WITH 4 SX CMT ON TOP. 1ST PLUG SHOT CASING AT 1300' UNABLE TO PULL CASING PUMPED 80 SX CMT. SHOT CASING AT 565' CASING WAS LOOSE. 2ND PLUG PUMPED 40 SX CMT AT 525'. 3RD PLUG PULLED TO 300' AND PUMPED 50 SX CMT. 4TH PLUG PUMPED 10 SX CMT FROM 0-40'. HOLE STAYED FULL.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 565' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Michael Maier

RECEIVED

(TECHNICIAN)

JAN 04 2002

INVOICED
DATE Jan 23-02
INV. NO. 2002061280

JAN 22 2002
1-22-02
KCC WICHITA

MP

Form C-2/3