

1 030447

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,177-0000

SE SW SE, SEC. 31, T 18 S, R 30 W/E  
330 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5249

Lease Name Delmar Whiting Well # 1

Operator: Osborn Heirs Company

County Lane 145.93 (Mississippi)

Name & Address P. O. Box 17968

Well Total Depth 4490 feet

San Antonio, TX 78286

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 217

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor White and Ellis Drilling, Inc. License Number 5420

Address 401 E. Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 23 Month: June Year: 19 85

Plugging proposal received from Judy Steiben

(company name) White & Ellis - Great Bend (phone) 316-792-2424

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2899' Anhydrite 2246-64'

1st plug at 2250' with 50 sx cement

2nd plug at 810' with 70 sx cement

3rd plug at 240' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 15 sx cement

6th plug to circulate rat hole with 15 sx cement  
Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 pm Day: 23 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement, 2nd plug at 810' with 70 sx

cement, 3rd plug at 240' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 15 sx cement, 6th plug to circulate rat hole with 15

sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
7-1-85  
JUL 01 1985

Remarks: Used 60/40 Pozmix 6% gel by Allied.

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this form.)

(XXX / did not) observe this plugging.

DATE 7-12-85

Signed Steve Durrant (TECHNICIAN)

INV. NO. 8912

6-23