

To: 1 071015  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
207 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,404 ~~0000~~ 1-17 79R  
SW SW SE, SEC. 33, T 18 S, R 30 W/EX  
330 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131  
Operator: Thunderbird Drilling Inc.  
Name & Address: P.O. Box 97  
Ellinwood, KS 67526

Lease Name Bryant A Well # 1  
County Lane 148.68  
Well Total Depth 4575 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 341

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 8:30 a.m. Day: 17 Month: 1 Year: 19 92

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4573' w/175 sx cement, PBSD 4160', Perfs at 4135-40'  
1st plug sand back to 4085' and dump 4 sx cement on top of sand through bailer,  
2nd plug shoot pipe at 1307', pump 125 sx cement down 4 1/2".  
Check backside.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN) 1-23-92

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:30 a.m. Day: 17 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dumped 4 sx cement on top of sand  
through bailer,  
2nd plug shot pipe at 1307', pumped 125 sx cement down 4 1/2".  
Backside would not take. It appears casing was cemented in hole at some point in time.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE FEB 07 1992  
INV. NO. 3444

Signed Dan Goodrow (TECHNICIAN) RAVL