

To: 1 070500
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9152

Operator: MAREXCO
Name: P.O. Box 706
Address: Edmond, OK 73083-0706

1-22-88

API NUMBER 15- 101-21,177-X0001

SE SW SE, SEC. 31, T 18 S, R 30 W/E

330 feet from S section line

1650 feet from E section line

Lease Name Delmar Whiting Well # 1

County Lane 150.80

Well Total Depth 4640 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9:20 a.m. Day: 22 Month: 1 Year: 19 88

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 4598' PBTD 4550' Perfs at 4490-92' Elevation 2899' GL

1st plug pump 1 sx hulls and 20 sx cement,

2nd plug pump 40 sx cement at 2185', 3rd plug pump 80 sx cement at 1300',

4th plug pump 40 sx cement at 240', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 p.m. Day: 22 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 100 lbs hulls and 20 sx cement to 4490',

2nd plug pumped 40 sx cement at 2100',

3rd plug pumped 80 sx cement at 1300',

4th plug pumped 40 sx cement at 240',

5th plug pumped 10 sx cement at 40-0', Pumped through casing.

Remarks: Used common cement by Sargent's. Recovered 2624' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (void) observe this plugging.

DATE 1-28-88

INV. NO. 19690

FEB 24 1988

MAR 24 1988

Signed Dan Jordan
(TECHNICIAN)