

To: 1090316  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-2.2 API NUMBER 15-101-21,661-0000  
W/2 SW SE, SEC. 35, T 18 S, R 30 W/4

TECHNICIAN'S PLUGGING REPORT

Operator License # 30581  
Operator: AGAPEX Limited  
Name & Address: 8095-D Holland Court  
Arvada, CO 80005

660 feet from S section line  
2310 feet from E section line  
Lease Name Buster Well # 1  
County Lane  
Well Total Depth 4650 151.12 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 222

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling Company, Inc. License Number 5104  
Address P.O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 4:30 p.m. Day: 22 Month: 8 Year: 1993  
Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Company, Inc. (phone) 316-792-5635

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2209'  
1st plug at 2209' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,  
3rd plug at 650' with 40 sx cement, 4th plug at 260' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X  
Operations Completed: Hour: 7:45 p.m. Day: 22 Month: 8 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 2209' with 50 sx cement,  
2nd plug at 1300' with 80 sx cement,  
3rd plug at 650' with 40 sx cement,  
4th plug at 260' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 31 1993  
8-31-93  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 9-2-93  
INV. NO. 38557

Signed [Signature] (TECHNICIAN)