

1 050896

APR 29 1987

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,123-0000

C SE/4, SEC. 19, T 18 S, R 31 W/E  
1320 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4311

Lease Name McKean Well # 1

Operator: Methanol Production Corporation  
Name &  
Address 165 South Union, Suite 500  
Lakewood, CO 80228

County Scott 95.55

Well Total Depth 2940 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 9 a.m. Day: 27 Month: 4 Year: 19 87

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 2940' Perfs at 2782-2790' Elevation 2967'GL

1st plug pump 2 sx hulls and 20 sx of common cement to 2700'

2nd plug perforate at 1450' and pump 150 sx of ATL down 4 1/2"

3rd plug pump 100 sx of ATL down 8 5/8"

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 29 Month: 4 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx common cement to 2700'

2nd plug at 1410' with 50 sx cement,

3rd plug at 390' with 50 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 5-11-87  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 1451' of 4 1/2" casing. Used common cement by Midwest Casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I will observe this plugging.

DATE 5-5-87

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 16764