

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20577-00-00
Spot: E2NENE Sec/Twnshp/Rge: 20-18S-31W
660 feet from N Section Line, 330 feet from E Section Line
Lease/Unit Name: BAILEY FAMILY TRUST Well Number: 1
County: SCOTT Total Vertical Depth: 4590 feet
Surface Casing Size: 8.625 feet: 226

Operator License No.: 31251
Op Name: WABASH ENERGY CORPORATION
Address: PO BOX 595
LAWRENCEVILLE, IL 62439

\$149.18

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/30/2003 3:30 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 2290' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/30/2003 6:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


1ST PLUG AT 2290' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
5-13-03
MAY 13 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY SWIFT SERVICES.

Plugged through: DP

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED

DATE 5-14-03

INVT. NO. 2003061529