

To: 1071062 5-1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,100-0000 33
C NW, SEC. 20, T. 18 S, R. 31 W
3960 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3857
Operator: Unico Inc.
Name & Address: P.O. Box 69
Commerce City, CO

Lease Name LTL Well # 1-20
County Scott
Well Total Depth 2800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 376

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497
Address Box F, Sublette, KS

Company to plug at: Hour: 10 a.m. Day: 1 Month: 5 Year: 19 92

Plugging proposal received from Ed Eves
(company name) Midwest Casing Pulling (phone) 316-675-8349

Perfs: 4 1/2" at 2799' w/100 sx cement, Perfs at 2762-77'
1st plug pump 200 lbs. hulls and 25 sx cement,
2nd plug shoot pipe at 1400' and squeeze 80 sx cement,
3rd plug shoot pipe at 300' and circulate with 125 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 1 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement,
2nd plug shot pipe at 1400' and dqueezed 80 sx cement,
3rd plug shot pipe at 300' and circulated with 125 sx cement.

Remarks: Used common cement by Midwest. No casing recovery.
(if additional description is necessary, use BACK of this form.)
I (did / did not) observe this plugging.

INVOICED
DATE 5-22-92
INV. NO. 35314

Signed Dan Goodrow (TECHNICIAN)
MAY 6 1992
5-6-92
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas