

1080251

TO: STATE CORPORATION COMMISSION

6-8

API NUMBER 15-171-20,091 - 000
C NW SE SEC. 21, T 18 S, R 31 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GRUBE WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SCOTT

OPERATOR LICENSE # ~~100~~ 101

KCC (D.S.)

WELL TOTAL DEPTH 4700 FEET

OPERATOR: KCC FEE FUND #990077-001 PRODUCTION CSG: SIZE 4 1/2" @ 2870' WITH 750 GAL LATEX

NAME AND 130 S MARKET RM 2078 SURFACE CASING: SIZE 8 5/8" @ 331' WITH 275 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CHEYENNE WELL SERVICE LICENSE NUMBER 6454

ADDRESS PO BOX 384 NESS CITY, KS 67560-0384

COMPANY TO PLUG AT: HOUR: 7:30 AM DAY: 08 MONTH: 06 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM KEVIN STRUBE

(COMPANY NAME) CHEYENNE WELL SERVICE (PHONE) 785-798-2282

WERE: PERFS AT 2754-57 & 2761-69

PERFORATE AT 1600'. RUN TUBING TO BOTTOM, PUMP 50 SX CEMENT WITH 200# HULLS. PULL TUBING TO 1600', CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT, PUMP DOWN 4 1/2" CASING. TRY TO CIRCULATE BETWEEN 8 5/8" X 4 1/2" ANNULUS.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 08 MONTH: 06 YEAR: 1999

ACTUAL PLUGGING REPORT

RAN TUBING IN HOLE TO 2693.71'. ALLIED PUMPED 50 SX CEMENT AND 200# HULLS. PULLED TUBING TO 1666'. PUMPED 20 BBL WATER, WELL DIDN'T CIRCULATE, PUMPED 50 SX CEMENT, 200# HULLS, 70 SX CEMENT. WELL CIRCULATED CEMENT TO SURFACE OF 4 1/2". PULLED TUBING TO 800'. PUMPED 30 SX CEMENT. PULLED TUBING OUT OF HOLE. TOPPED OFF WITH 10 SX CEMENT DOWN 4 1/2". PUMPED DOWN 4 1/2 X 8 5/8 ANNULUS 140 SX CEMENT. SHUT IN AT 100#.

6
17
99

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D. Shull
(TECHNICIAN) FORM CP-2/3