

To: 1 080171  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-171-20,041-0000

TECHNICIAN'S PLUGGING REPORT

Operator License / 3857

Operator: UNICO, Inc.  
Name & Address: 1921 Bloomfield Blvd.  
Farmington, NM 87401

1-21  
App. C NW, SEC. 22, T 18 S, R 31 W  
4000 feet from S section line  
4000 feet from E section line  
Cauthon

Lease Name Margaret C. Well # 1  
County Scott 90.61

Well Total Depth 2788 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Well Service License Number 6454

Address P.O. Box 384, Ness City, KS 67560-0384

Company to plug at: Hour: 9:30 a.m. Day: 21 Month: 1 Year: 19 98

Plugging proposal received from Robert Emberton

(company name) UNICO, Inc. (phone) 316-872-1762

Work: 5 1/2" at 2784' w/175 sx cement, PBSD 2769', Perfs at 2753-61'

1st plug set CIBP at 2700',

2nd plug at 2200' with 50 sx cement,

3rd plug at 1400' with 80 sx cement,

4th plug at 400' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5 p.m. Day: 21 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug L-K Wireline set CIBP at 2400' with 4 sx cement on top,

2nd plug perforated at 1400', two holes, pumped 80 sx cement, displaced to 900',

3rd plug shot casing off at 850' and pulled up to 420'. Pumped 50 sx cement,

4th plug pulled up to 40' and topped off with 13 sx cement.

1-27-98  
Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 850' of 5 1/2" casing.  
(Additional description is necessary, use BACK of this form.)

DATE (did / XXXXXXXX) observe this plugging.

INV. NO. 50005

Signed Kevin D. Shabo (TECHNICIAN)

1-21 JUN 17 1998