

1060361

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 171-20,285 -0000
30' W of C
NE NE SE, SEC. 23, T 18 S, R 31 W/R
2310 feet from ~~XXX~~ ^N SE Corner of section line
360 feet from ~~XXX~~ ^W SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Eitel Well # 1-23

Operator: Landmark Oil Exploration, Inc.
Name & Address 105 S. Broadway, Suite 1040
Wichita, KS 67202

County Scott

Well Total Depth 4600 ^{109.50} feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 617 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 9:00 pm Day: 8 Month: October Year: 19 84

Plugging proposal received from Terry McRae

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2240' with 50 sx cement

2nd plug at 1470' with 50 sx cement

3rd plug at 350' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:00 pm Day: 8 Month: October Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 2240' with 50 sx cement, 2nd plug at 1470' with 50 sx cement, 3rd plug at 350' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.
(If additional description is necessary, use BACK of this form.)

NOV 12 1984
10-12-84

NOTICED

DATE 10-15-84

INV. NO. 4311 10-8

NOV 19 1984

Signed Paul A. Luthie (TECHNICIAN)