



CPZ

15-101-20015-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 26 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Petroleum, Inc. has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling & Petroleum Resources,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Foster Well No. C-1

Location: NE-SE-NE Sec. 34 Twp. 16 Rge. (E)(W) 27

County: Lane Total Depth 4577' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Mason was instructed to plug the well as follows:

290'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 100 Sx.  
cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

*A. L. Pichok*  
Conservation Division Agent