



KS 101-20006-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
18-26-70  
OCT 26 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated,

Complete Address: 1625 Wichita Plaza, Wichita, Kansas.

Lease Name: Cramer Well No. 1

Location: CSW-NE Sec. 20 Twp. 18 Rge. (E)(W) 30

County: Lane Total Depth 4655' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hunt was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated with 180 Sx.  
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent