



15-101-20039-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

RECEIVED STATE CORPORATION COMMISSION 9-11-72 CONSERVATION DIVISION Wichita, Kansas

Dear Sir:

Mr. Desn Ulrich of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company & Mull Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Steele-Whiteman Well No. 1

Location: CNE-SW Sec. 21 Twp. 18 Rge. (E)(W) 30

County: Lane Total Depth 3323' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

239'--8 5/8" Surface casing, cement circulated with 150 Sx. Top of Dakota section @ 825'.

Circulate hole with heavy mud. Pull DP to 1075' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

[Signature] Conservation Division Agent